# Corrigo E Ventilation

## List of network variables for EXOline and modbus communication

Covers all versions of Corrigo E Ventilation from revision 2.3-1-01


Revision: 9
Date: 09-07-07



**Head Office Sweden**
Phone: +46 31 720 02 00
Web: www.regin.se
Mail: info@regin.se

**Sales Offices**
France: +33 14 171 46 46
Germany: +49 30 77 99 40
Spain: +34 91 473 27 65
Hong Kong: +852 24 07 02 81
Singapore: +65 67 47 82 33

REGIN
THE CHALLENGER IN BUILDING AUTOMATION

# Table of contents

# 1. Corrigo E with modbus and EXOline communication

**Introduction**

Corrigo E Ventilation is a pre-programmed application controller for controlling of an air handling unit. This controller can either be stand-alone or built-in in an existing EXO-project, in both case it's configured by the display or by a configuration tool on pc (E Tool). This document will describe all the signals that are accessible via EXOline or Modbus. This document will not describe how to create an EXO project.

**Signal types**

All signals that are accessible from a SCADA system are described further in this document. The signals that have a default value are settings that can be changed from SCADA, the signals without default values is actual values and they can not be changed from SCADA.

**EXOL Type**

The EXOL type of the signals:

R = Real (-3.3E38 - 3.3E38)

I = Integer (-32768 - 32767)

X = Index (0 - 255)

L = Logic (0/1)

**Modbus Type**

The Modbus type of the signals (type in the list below):

1 = Coil Status Register (Modbus function = 1, 5 and 15)

2 = Input Status Register (Modbus function = 2)

3 = Holding Register (Modbus function = 3, 6 and 16)

4 = Input Register (Modbus function = 4)

Supported Modbus functions:

1 = Read Coils

2 = Read Discrete Input

3 = Read Holding Register

4 = Read Input Register

5 = Write Single Coil

6 = Write Single Register

15 = Write Multiple Coils

16 = Write Multiple Registers

**Max 47 register**

Max 47 register can be read in one message

**Communication limits** The modbus master must wait for a minimum of 3.5 charactertimes (4ms at 9600 bps) between two messages. When the modbus master communicate with more than one Corrigo E controller on the same communication line (RS485), the modbus master must wait for a minimum of 14 charactertimes (16ms at 9600bps) between the answer and the first question for the next controller.

In the Corrigo E controller there is a limit of 10 fast communications in every half minute, the other communications will have a delayed answer of approximately 1 second.

**Scale factor Modbus** Real signals have scale factor 10 except the time settings signals that have scale factor 100 and Air flow signals that have scale factor 1 for modbus communication. Integer, Index and Logic has always scale factor 1.

**Modbus activation** Corrigo uses the same port for both Modbus communication and for EXOline communication. If you try to communicate with a Modbus-activated unit using E Tool or other EXOline communication the input port will will automatically adapt itself after approx. 1 second. The port will remain in EXO-mode until 10 seconds of communication inactivity have passed after which it will revert to Modbus mode.

**Modbus limitations** In order not to overload the Corrigo processor, a restriction of maximum 60 communications per minut has been set.

**Modbus wiring etc.** A protocol such as Modbus consists of several layers (OSI-model). The bottom layer is always the physical layer, number of wires and signal levels. the next layer describes the communication digits (number of data bits, stop-bits, parity etc). Then come the layers describing the Modbus specific functions (number of digits per message, the meaning of different messages etc).

For Modbus, the bottom layer can be RS485, RS422 or RS232.

**RS485 contra RS422** RS485 and RS422 are the electric part of the protocol, i. e. the physical layer. RS485 has two connections, A and B. Often there is also a protecive earth (N on EXOmodules). RS485 units are always connected A → A and B → B. RS485 is so called half duplex communication: Communication can only go in one direction at a time; i. e. the master will first send an enquiery and will thereafter listen for the reply. A and B are used for both transmission and reception.

RS422 is a full duplex communication which means you need 4 wires, 2 for transmit (Tx+ and Tx-) and 2 for receive (Rx+ and Rx-). Tx is used to transmit and Rx to receive which means that Tx in one unit must be connected to Rx in the other and vice versa. As for signal levels etc. RS422 and RS485 are identical.

To interconnect RS485 and RS422: On the RS422 unit connect Tx+ with Rx+ and Tx- with Rx-. We have now changed a 4-wire system to a 2-wire system and can connect them to A and B on the RS485 unit. Which goes whare is something you most often need to find out by trial and error. Incorrect polarity will just give non-function but cannot harm either unit.



Bitrate, two stop bits, parity is the next layer

These settings must correspond to the settings in the master unit. Find out how the master is set and then give the Corrigo E the same settings.

Parity can be set to odd, even or none. if none is chosen you normally set two stop-bits instead but this is not necessary. If odd or even is chosen you can only have one stop-bit. otherwise there will be too many bits altogether: 1 start-bit, 8 data-bits, 1 parity-bit and 1 stop-bit give a total of 11 bits which is maximum.

# 2. Actual/Setpoint

## 2.1. General

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation2.Cor_OutDoorTemp(0) | R,4 | 1 | | Outdoor temperature, (Read only) |
| Ventilation2.Cor_OutDoorTemp(0) | R,3 | 392 | | Outdoor temperature (Can be modified if it's not connected to a physical analog input). |
| Ventilation2.Cor_Efficiency | R,4 | 2 | | Efficiency in % for exchanger |
| Ventilation2.Cor_RunMode | X,4 | 3 | | 0=Stopped,<br>1=Starting up,<br>2=Starting reduced speed,<br>3=Starting full speed,<br>4=Starting normal run,<br>5=Normal run,<br>6=Support control heating,<br>7=Support control cooling,<br>8=CO2 run,<br>9=Night cooling,<br>10=Full speed stop,<br>11=Stopping fan |
| Ventilation2.Cor_SAFRunTime | R,4 | 4 | | Running time (hour) supply air fan |
| Ventilation2.Cor_EAFRunTime | R,4 | 5 | | Running time (hour) exhaust air fan |
| TimePro.TimeGroupFanFullSpeed | L,2 | 1 | | Is set if timechannel full speed is active |
| TimePro.TimeGroupFanHalfSpeed | L,2 | 2 | | Is set if timechannel reduced speed is active |
| TimePro.TimeGroupCor_ExtraTimeGroup1 | L,2 | 3 | | Is set if timer output 1 is active |
| TimePro.TimeGroupCor_ExtraTimeGroup2 | L,2 | 4 | | Is set if timer output 2 is active |
| TimePro.TimeGroupCor_ExtraTimeGroup3 | L,2 | 5 | | Is set if timer output 3 is active |
| TimePro.TimeGroupCor_ExtraTimeGroup4 | L,2 | 6 | | Is set if timer output 4 is active |
| TimePro.TimeGroupCor_ExtraTimeGroup5 | L,2 | 7 | | Is set if timer output 5 is active |

| | | | | |
|---|---|---|---|---|
| Ventilation2.Cor_ExtendedRunActiveFull | L,2 | 8 | | Is set if extended operation full speed |
| Ventilation2.Cor_ExtendedRunActive Half | L,2 | 9 | | Is set if extended operation half speed |
| Ventilation2.Cor_ExtendedRunMin | I,4 | 6 | | Number of minutes extended operation |
| Ventilation2.Cor_HeatPumpStart(0) | L,2 | 85 | | Start signal Heat Pump |
| Ventilation2.Cor_ExchPumpStart | L,2 | 86 | | Start signal Exchanger |
| Ventilation2.Cor_CoolPumpStart | L,2 | 87 | | Start signal Cool Pump |
| Ventilation1.Cor_HeatPumpLimit | R,3 | 403 | 10℃ | If lowe r outdoortemp the heating pump is not stoped |

# 2.2. Supply,Exhaust and Room temperatures

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation2.Cor_SupplyAirTemp | R,4 | 7 | | Supply air temperature |
| Ventilation1.Cor_SupplySetpoint | R,3 | 1 | 18℃ | Setpoint supply air temperature when constant supply air temperature function |
| Ventilation4.Cor_SupplyPID_SetP | R,4 | 8 | | Calculated setpoint supply air temperature when outdoor compensated control function |
| Ventilation4.Cor_Curve1_X1 | R,3 | 2 | -20℃ | Outdoortemp for first curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_X2 | R,3 | 3 | -15℃ | Outdoortemp for second curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_X3 | R,3 | 4 | -10℃ | Outdoortemp for third curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_X4 | R,3 | 5 | -5℃ | Outdoortemp f or fourth curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_X5 | R,3 | 6 | 0℃ | Outdoortemp fo r fifth curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_X6 | R,3 | 7 | 5℃ | Outdoortemp fo r sixth curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_X7 | R,3 | 8 | 10℃ | Outdoortemp f or seventh curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_X8 | R,3 | 9 | 15℃ | Outdoortemp f or eighth curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_Y1 | R,3 | 10 | 25℃ | Setpoint for first curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_Y2 | R,3 | 11 | 24℃ | Setpoint for second curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_Y3 | R,3 | 12 | 23℃ | Setpoint for third curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_Y4 | R,3 | 13 | 23℃ | Setpoint for fourth curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_Y5 | R,3 | 14 | 22℃ | Setpoint for fifth curvepoint for outdoor compensated setpoint |

| | | | | |
|---|---|---|---|---|
| Ventilation4.Cor_Curve1_Y6 | R,3 | 15 | 20℃ | Setpoint for sixth curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_Y7 | R,3 | 16 | 18℃ | Setpoint for seventh curvepoint for outdoor compensated setpoint |
| Ventilation4.Cor_Curve1_Y8 | R,3 | 17 | 18℃ | Setpoint for eight curvepoint for outdoor compensated setpoint |
| Ventilation2.Cor_ExhaustAirTemp | R,4 | 9 | | Exhaust air temp |
| Ventilation1.Cor_ExhaustSetpoint | R,3 | 18 | 21℃ | Setpoi nt exhaust air temp if exhaust air temp control function |
| Ventilation2.Cor_RoomTemp1 | R,4 | 10 | | Room temperature 1 |
| Ventilation1.Cor_RoomSetP | R,3 | 19 | 21℃ | Room setpoint if room temp control function |
| Ventilation2.Cor_RoomTemp2 | R,4 | 11 | | Room temperature 2 |
| Ventilation2.Cor_RoomTemp | R,4 | 135 | | Room temperature 1 and 2 |
| Ventilation1.Cor_NeedHeatStart | R,3 | 20 | 15℃ | Room tem p for start the unit if intermittent heating control is active |
| Ventilation1.Cor_NeedHeatStop | R,3 | 21 | 21℃ | Room temp for stop the unit if intermittent heating control is active |
| Ventilation2.Cor_NeedHeatActive | L,2 | 10 | | Is set if ongoing support heating |
| Ventilation1.Cor_NeedCoolStart | R,3 | 22 | 30℃ | Room tem p for start the unit if intermittent cooling control is active |
| Ventilation1.Cor_NeedCoolStop | R,3 | 23 | 28℃ | Room temp for stop the unit if intermittent cooling control is active |
| Ventilation2. Cor_NeedCoolActive | L,2 | 11 | | Is set if ongoing support cooling |
| Ventilation2. Cor_NeedRunTime | I,4 | 12 | | Number of minutes in ongoing support heating/cooling |
| Ventilation2.Cor_HeatCV1(0) | R,4 | 119 | | Control signal heating Y1 (0-10 V) |
| Ventilation2.Cor_ExchCV1 | R,4 | 120 | | Control signal exchanger Y2 (0-10 V) |
| Ventilation2.Cor_CoolCV1 | R,4 | 121 | | Control signal cooler Y3 (0-10 V) |
| Ventilation2.Cor_Split | R,4 | 125 | | Control signal split (0-10 V) |
| Ventilation4.Cor_SupplyPID_Output | R,4 | 126 | | Supply controller output (0-100 %) |
| Ventilation4.Cor_ExhaustPID_Output | R,4 | 127 | | Exhaust controller output (0-100 %) |
| Ventilation4.Cor_RoomPID_Output | R,4 | 132 | | Room controller output (0-100 %) |
| Ventilation1.Cor_SupplySetpointMax | R,3 | 404 | | Max limit of supply setpoint when cascade control |
| Ventilation1.Cor_SupplySetpointMin | R,3 | 405 | | Min limit of supply setpoint when cascade control |

## 2.3. SAF/EAF Pressure and Flow

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation2.Cor_SAFPressure | R,4 | 13 | | Supply air fan pressure (Pa) |
| Ventilation1.Cor_SAFFullspeedPressure | R,3 | 24 | 500Pa | Setpoint full speed supply air fan pressure |

| | | | | |
|---|---|---|---|---|
| Ventilation1.Cor_SAFHalfspeedPressure | R,3 | 25 | 250Pa | Setpoint reduced speed supply air fan pressure |
| Ventilation2.Cor_EAFPressure | R,4 | 14 | | Exhaust air fan pressure (Pa) |
| Ventilation1.Cor_EAFFullspeedPressure | R,3 | 26 | 500Pa | Setpoint full speed exhaust air fan pressure |
| Ventilation1.Cor_EAFHalfspeedPressure | R,3 | 27 | 250Pa | Setpoint reduced speed exhaust air fan pressure |
| Ventilation2.Cor_SAFAirFlow | R,4 | 15 | | Supply air fan flow (m3/h). Scale factor = 1 |
| Ventilation1.Cor_SAFFullspeedAirFlow | R,3 | 28 | 2000 m3/h | Setpoint full speed supply air fan flow. Scale factor = 1 |
| Ventilation1.Cor_SAFHalfspeedAirFlow | R,3 | 29 | 1000 m3/h | Setpoint reduced speed supply air fan flow. Scale factor = 1 |
| Ventilation2.Cor_EAFAirFlow | R,4 | 16 | | Exhaust air fan flow (m3/h) Scale factor = 1 |
| Ventilation1.Cor_EAFFullspeedAirFlow | R,3 | 30 | 2000 m3/h | Setpoint full speed exhaust air fan flow. Scale factor = 1 |
| Ventilation1.Cor_EAFHalfspeedAirFlow | R,3 | 31 | 1000 m3/h | Setpoint reduced speed exhaust air fan flow. Scale factor = 1 |
| Ventilation1.Cor_Comp1Pressure | R,3 | 414 | 0 | Pressure compensation at breakpoint 1 |
| Ventilation1. Cor_Comp1Temp | R,3 | 415 | -20 | Outdoor temp breakpoint 1 (must be lower than breakpoint 2 temp) |
| Ventilation1.Cor_Comp2Pressure | R,3 | 416 | 0 | Pressure compensation at breakpoint 2 |
| Ventilation1.Cor_Comp2Temp | R,3 | 417 | 10 | Outdoor temp breakpoint 2 (must be higher than breakpoint 1 temp) |
| Ventilation1. Cor_CompSAFOnly | L,1 | 7 | 0 | Is set if only SAF pressure should be compensated |
| Ventilation1.Cor_SAFFullspeedOutput | R,3 | 424 | 75 % | Output signal (0-100%) full speed SAF if Frequency control manual |
| Ventilation1.Cor_SAFHalfspeedOutput | R,3 | 425 | 50 % | Output signal (0-100%) half speed SAF if Frequency control manual |
| Ventilation1.Cor_EAFFullspeedOutput | R,3 | 426 | 75 % | Output signal (0-100%) full speed EAF if Frequency control manual |
| Ventilation1.Cor_EAFHalfspeedOutput | R,3 | 427 | 50 % | Output signal (0-100%) half speed EAF if Frequency control manual |
| Ventilation2.Cor_SAFStart1(0) | L,2 | 81 | | Start signal full speed supply air fan |
| Ventilation2.Cor_EAFStart1 | L,2 | 82 | | Start signal full speed exhaust air fan |
| Ventilation2.Cor_SAFStart2 | L,2 | 83 | | Start signal half speed supply air fan |
| Ventilation2.Cor_EAFStart2 | L,2 | 84 | | Start signal half speed exhaust air fan |
| Ventilation2.Cor_SAFFrequencyStart | L,2 | 88 | | Start signal frequencer supply air fan |
| Ventilation2.Cor_EAFFrequencyStart | L,2 | 89 | | Start signal frequencer exhaust air fan |
| Ventilation2.Cor_SAF | R,4 | 122 | | Control signal supply air fan (0-10 V) |
| Ventilation2.Cor_EAF | R,4 | 123 | | Control signal exhaust air fan (0-10 V) |
| Ventilation4.Cor_SAFPID_Output | R,4 | 128 | | SAF controller output (0-100 %) |
| Ventilation4.Cor_EAFPID_Output | R,4 | 129 | | EAF controller output (0-100 %) |
| Ventilation2.Cor_ExtSAFControl | R,4 | 151 | | External SAF signal control (%) |
| Ventilation2.Cor_ExtEAFControl | R,4 | 152 | | External EAF signal control (%) |
| Ventilation2. Cor_SAFPressure2 | R,4 | 153 | | Pressure transmitter 2 supply air (Pa) |

| | | | | |
|---|---|---|---|---|
| Ventilation2.Cor_SAFAirFlow2 | R,4 | 154 | | Calculated air flow m3/sek supply air 2 airflow = Cor_AirFlowK * Cor_SAFPressure2^Cor_AirFlowx) |
| Ventilation1.Cor_SAFAirFlowK | R,3 | 443 | 100 | K-constant for calculating air flow SAF airflow = Cor_AirFlowK * Cor_SAFPressure^Cor_AirFlowx |
| Ventilation1.Cor_SAFAirFlowx | R,3 | 444 | 0.5 | X-constant for calculating air flow SAF |
| Ventilation1.Cor_EAFAirFlowK | R,3 | 445 | 100 | K-constant for calculating air flow EAF airflow = Cor_AirFlowK * Cor_SAFPressure^Cor_AirFlowx |
| Ventilation1.Cor_EAFAirFlowx | R,3 | 446 | 0.5 | X-constant for counting air flow EAF |
| Ventilation1.Cor_EAFFrequencyFact | R,3 | 447 | 1 | Factor for controlling EAF if CAV fan control is configured (EAF is controlled by SAF with this factor) |

## 2.4. CO2

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation2.Cor_CO2Sensor | R,4 | 17 | | CO2 (ppm) |
| Ventilation1.Cor_CO2Setpoint | R,3 | 32 | 1000ppm | Setpoint CO2 |
| Ventilation2.Cor_DemandCO2Active | L,2 | 12 | | Is set if ongoing support CO2 |
| Ventilation2.Cor_DemandRunTime | I,4 | 18 | | Number of minutes support run time CO2 |
| Ventilation4.Cor_CO2PID_Output | R,4 | 131 | | CO2 controller output (0-100 %) |

## 2.5. Frost protection

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation2.Cor_FrostprotectionTemp | R,4 | 19 | | Frost protection temp |
| Ventilation1.Cor_FrostProtSPStop | R,3 | 33 | 25℃ | Setpoi nt frost protection if the ventilation unit is stoped |
| Ventilation1.Cor_FrostProtPGain | R,3 | 34 | 5° | P-Gain fr ost protection when running (alarm limit+PGain) |
| Ventilation4.Cor_FrostPID_Output | R,4 | 130 | | Frost protection controller output if ventilation unit is stoped (0-100 %) |

## 2.6. Extract air temp/De-icing exchanger

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation2.Cor_ExtractAirTemp | R,4 | 20 | | Extract air temp |
| Ventilation2.Cor_DeIcingTemp | R,4 | 21 | | De-icing temp exchanger |
| Ventilation1.Cor_DeIcingSetpoint | R,3 | 35 | -3° | Setpoin t de-icing temp |
| Ventilation1.Cor_DeIcingHyst | R,3 | 36 | 1℃ | Hysteresis for stop of de-icing |
| Ventilation2.Cor_DeIcingActive | L,2 | 13 | | Is set if ongoing de-icing |
| Ventilation2.Cor_DeIcingTime | X,4 | 22 | | Number of minutes for ongoing de-icing |
| Ventilation4.Cor_DeIcePID_Output | R,4 | 133 | | De-icing controller output (0-100 %) |

## 2.7. Humidity room/duct

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation2.Cor_HumidityRoom | R,4 | 23 | | Humidity room |
| Ventilation1.Cor_HumiditySetpoint | R,3 | 37 | 50%RH | Setpoint humidity room |
| Ventilation2.Cor_HumidityDuct | R,4 | 24 | | Humidity duct |
| Ventilation1.Cor_HumidityMaxDuct | R,3 | 38 | 80%RH | Max limit humidity duct |
| Ventilation1.Cor_HumidityHyst | R,3 | 39 | 20%RH | Hysteresis to start humidity control after stop max limitation |
| Ventilation2.Cor_Humidity | R,4 | 124 | | Control signal humidity (0-10 V) |
| Ventilation4.Cor_HumidityPID_Output | R,4 | 134 | | Humidity controller output (0-100 %) |
| Ventilation1.Cor_HumidityMaxDiff | R,3 | 418 | 10 %RH | Max allowed difference between setpoint and humidity in room before alarm |
| Ventilation1.Cor_HumidityStartLimit | R,3 | 419 | 15 %RH | Start limit in % to start digital output signal "Cor_HumidityStart(0)" |
| Ventilation1.Cor_HumidityStopLimit | R,3 | 420 | 5 %RH | Stop limit in % to stop digital output signal "Cor_HumidityStart(0)" |

## 2.8. Additional sensor/External setpoint

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation2.Cor_ExtraSensor | R,4 | 25 | | Additional sensor / External setpoint |

## 2.9. Extra Unit

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation1.Cor_ExtraUnitFunc | X,3 | 434 | 0 | Start/Stop function Extra Unit:<br>0=Off<br>1=Always running<br>2=Running if unit is running |
| Ventilation1.Cor_ExtraUnitSetP | R,3 | 435 | 18 ℃ | Setpoi nt Extra Unit |
| Ventilation1.Cor_ExtraUnitPID1Mode | X,3 | 436 | 0 | Control mode Extra Unit<br>0=Heating Controller<br>1=Cooling Controller |
| Ventilation2.Cor_ExtraUnitTemp(0) | R,4 | 150 | | Extra Unit temp |

## 2.10. Recirculation

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation1.Cor_RecycleSetP | R,3 | 439 | 18 ℃ | Recircul ation setpoint |
| Ventilation1.Cor_RecycleMaxRoomTemp | R,3 | 440 | 25 ℃ | If higher room temp during Recirculat ion run recirculation damper is closed and fresh air damper is opend |
| Ventilation1.Cor_RecycleSAFOffset | R,3 | 441 | 0 | Setpoint offset if pressure/flow controlled SAF (Pa) |
| Ventilation1.Cor_RecycleEAFOffset | R,3 | 442 | 0 | Setpoint offset if pressure/flow controlled EAF (this is not used) |
| Ventilation1.Cor_RecycleTempControl | L,1 | 4 | 0 | Enable supply air temp control during recirculation run:<br>0=No temp control<br>1=heating/cooling<br>2=only heating<br>3=only cooling |
| Ventilation1.Cor_RecycleNightCool | L,1 | 5 | 0 | Enable the night cool function during Recirculation run |
| Ventilation1.Cor_RecycleExtraTimeGroup5 | L,1 | 6 | 0 | Use ExtraTimeGroup 5 to start Recirculation run |

# 3. Input/Output

## 3.1. Analogue inputs

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation2.Cor_AnalogInput1(0) | R,4 | 26 | | The scaled and filtered value of AI1 |
| Ventilation2.Cor_AnalogInput2 | R,4 | 27 | | The scaled and filtered value of AI2 |
| Ventilation2.Cor_AnalogInput3 | R,4 | 28 | | The scaled and filtered value of AI3 |
| Ventilation2.Cor_AnalogInput4 | R,4 | 29 | | The scaled and filtered value of AI4 |
| Ventilation1.Cor_Ai1(0) | X,4 | 34 | | Connected signal on AI1:<br>0=Not used<br>1=Outdoortemp<br>2=Supplytemp<br>3=Exhausttemp<br>4=Roomtemp1<br>5=Roomtemp2<br>6=Extracttemp<br>7=Extrasensor<br>8=SAF pressure<br>9=EAF pressure<br>10=Deicingtemp<br>11=Frost prot.temp<br>12=CO2<br>13=Humidity room<br>14=Humidity duct<br>15=Extra unit temp<br>16=External SAF control<br>17=External EAF control<br>18=SAF pressure 2 |
| Ventilation1.Cor_Ai2 | X,4 | 35 | | Connected signal on AI2:<br>(See signal list for AI1) |
| Ventilation1.Cor_Ai3 | X,4 | 36 | | Connected signal on AI3:<br>(See signal list for AI1) |
| Ventilation1.Cor_Ai4 | X,4 | 37 | | Connected signal on AI4:<br>(See signal list for AI1) |

# 3.2. Digital inputs

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| QDig.DI1 | L,2 | 14 | | Value of DI1 |
| QDig.DI2 | L,2 | 15 | | Value of DI2 |
| QDig.DI3 | L,2 | 16 | | Value of DI3 |
| QDig.DI4 | L,2 | 17 | | Value of DI4 |
| QDig.DI5 | L,2 | 18 | | Value of DI5 |
| QDig.DI6 | L,2 | 19 | | Value of DI6 |
| QDig.DI7 | L,2 | 20 | | Value of DI7 |
| QDig.DI8 | L,2 | 21 | | Value of DI8 |
| Ventilation1.Cor_Di1(0) | X,4 | 42 | | Connected signal on DI1:<br>0=Not used<br>1=SAF-Ind<br>2=EAF-Ind<br>3=P1-Heating<br>4=P1-Exchanger<br>5=P1-Cooling<br>6=Filter alarm<br>7=Fire alarm<br>8=Fire damper-ind<br>9=Ext run 1/1<br>10=Ext run ½<br>11=External alarm<br>12=External switch<br>13=Flow guard<br>14=Rot.sent.exch<br>15=De-icing<br>16=Frostprotection<br>17=Overheatprotection<br>18=Recirculation run<br>19=Change over |
| Ventilation1.Cor_Di2 | X,4 | 43 | | Connected signal on DI2:<br>(See signal list for DI1) |
| Ventilation1.Cor_Di3 | X,4 | 44 | | Connected signal on DI3:<br>(See signal list for DI1) |
| Ventilation1.Cor_Di4 | X,4 | 45 | | Connected signal on DI4:<br>(See signal list for DI1) |
| Ventilation1.Cor_Di5 | X,4 | 46 | | Connected signal on DI5:<br>(See signal list for DI1) |
| Ventilation1.Cor_Di6 | X,4 | 47 | | Connected signal on DI6:<br>(See signal list for DI1) |
| Ventilation1.Cor_Di7 | X,4 | 48 | | Connected signal on DI7:<br>(See signal list for DI1) |
| Ventilation1.Cor_Di8 | X,4 | 49 | | Connected signal on DI8:<br>(See signal list for DI1) |

# 3.3. Universal inputs

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation2.Cor_AnalogInput5 | R,4 | 30 | | The scaled and filtered value of UAI1 |
| Ventilation2.Cor_AnalogInput6 | R,4 | 31 | | The scaled and filtered value of UAI2 |
| Ventilation2.Cor_AnalogInput7 | R,4 | 32 | | The scaled and filtered value of UAI3 |
| Ventilation2.Cor_AnalogInput8 | R,4 | 33 | | The scaled and filtered value of UAI4 |
| Ventilation1.Cor_UAi1 | X,4 | 38 | | Connected signal on UAI1:<br>0=Not used<br>1=Outdoortemp<br>2=Supplytemp<br>3=Exhausttemp<br>4=Roomtemp1<br>5=Roomtemp2<br>6=Extracttemp<br>7=Extrasensor<br>8=SAF pressure<br>9=EAF pressure<br>10=Deicingtemp<br>11=Frost prot.temp<br>12=CO2<br>13=Humidity room<br>14=Humidity duct<br>15=Extra unit temp<br>16=External SAF control<br>17=External EAF control<br>18=SAF pressure 2 |
| Ventilation1.Cor_UAi2 | X,4 | 39 | | Connected signal on UAI2:<br>(See signal list for UAI1) |
| Ventilation1.Cor_UAi3 | X,4 | 40 | | Connected signal on UAI3:<br>(See signal list for UAI1) |
| Ventilation1.Cor_UAi4 | X,4 | 41 | | Connected signal on UAI4:<br>(See signal list for UAI1) |
| QDig.DI9 | L,2 | 22 | | Value of UDI1 |
| QDig.DI10 | L,2 | 23 | | Value of UDI2 |
| QDig.DI11 | L,2 | 24 | | Value of UDI3 |
| QDig.DI12 | L,2 | 25 | | Value of UDI4 |

| | | | | |
|---|---|---|---|---|
| Ventilation1.Cor_UDi1 | X,4 | 50 | | Connected signal on UDI1:<br>0=Not used<br>1=SAF-Ind<br>2=EAF-Ind<br>3=P1-Heating<br>4=P1-Exchanger<br>5=P1-Cooling<br>6=Filter alarm<br>7=Fire alarm<br>8=Fire damper-ind<br>9=Ext run 1/1<br>10=Ext run ½<br>11=External alarm<br>12=External switch<br>13=Flow guard<br>14=Rot.sent.exch<br>15=De-icing<br>16=Frostprotection<br>17=Overheatprotection<br>18=Recirculation run<br>19=Change over |
| Ventilation1.Cor_UDi2 | X,4 | 51 | | Connected signal on UDI2:<br>(See signal list for UDI1) |
| Ventilation1.Cor_UDi3 | X,4 | 52 | | Connected signal on UDI3:<br>(See signal list for UDI1) |
| Ventilation1.Cor_UDi4 | X,4 | 53 | | Connected signal on UDI4:<br>(See signal list for UDI1) |

# 3.4. Analogue outputs

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| QAnaOut.AQ1 | R,4 | 54 | | Value of AO1 |
| QAnaOut.AQ2 | R,4 | 55 | | Value of AO2 |
| QAnaOut.AQ3 | R,4 | 56 | | Value of AO3 |
| QAnaOut.AQ4 | R,4 | 57 | | Value of AO4 |
| QAnaOut.AQ5 | R,4 | 58 | | Value of AO5 |
| Ventilation1.Cor_Ao1(0) | X,4 | 59 | | Connected signal on AO1:<br>0=Not used<br>1=Y1-Heating<br>2=Y2-Exchanger<br>3=Y3-Cooling<br>4=SAF<br>5=EAF<br>6=Y6-Humidity<br>7=Sequence<br>8=Extra unit<br>9=Heat/Cool (change over) |
| Ventilation1.Cor_Ao2 | X,4 | 60 | | Connected signal on AO2:<br>(See signal list for AO1) |

| | | | | |
|---|---|---|---|---|
| Ventilation1.Cor_Ao3 | X,4 | 61 | | Connected signal on AO3:<br>(See signal list for AIO) |
| Ventilation1.Cor_Ao4 | X,4 | 62 | | Connected signal on AO4:<br>(See signal list for AO1) |
| Ventilation1.Cor_Ao5 | X,4 | 63 | | Connected signal on AO5:<br>(See signal list for AO1) |

# 3.5. Digital outputs

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| QDig.Dq1 | L,2 | 26 | | Value of DO1 |
| QDig.Dq2 | L,2 | 27 | | Value of DO2 |
| QDig.Dq3 | L,2 | 28 | | Value of DO3 |
| QDig.Dq4 | L,2 | 29 | | Value of DO4 |
| QDig.Dq5 | L,2 | 30 | | Value of DO5 |
| QDig.Dq6 | L,2 | 31 | | Value of DO6 |
| QDig.Dq7 | L,2 | 32 | | Value of DO7 |

| | | | | |
|---|---|---|---|---|
| Ventilation1.Cor_Do1(0) | X,4 | 64 | | Connected signal on DO1:<br>0 = Not Used<br>1 = SAFStart1<br>2 = EAFStart1<br>3 = SAFStart2<br>4 = EAFStart2<br>5 = HeatingPumpStart<br>6 = ExchangerStart<br>7 = CoolingPumpStart<br>8 = FireDamper<br>9 = SumAlarm<br>10 = SumAlarmA<br>11 = SumAlarmB<br>12 = SAFFrequencyStart<br>13 = EAFFrequencyStart<br>14 = HeatingActivate<br>15 = ExchangerActivate<br>16 = CoolingActivate<br>17 = RecycleAirDamper<br>18 = FreshAirDamper<br>19 = ExtractAirDamper<br>20 = HeatingIncrease<br>21 = HeatingDecrease<br>22 = ExchangerIncrease<br>23 = ExchangerDecrease<br>24 = CoolingIncrease<br>25 = CoolingDecrease<br>26 = HeatStep1<br>27 = HeatStep2<br>28 = HeatStep3<br>29 = HeatStep4<br>30 = CoolStep1<br>31 = CoolStep2<br>32 = CoolStep3<br>33 = TimeChannel1<br>34 = TimeChannel2<br>35 = TimeChannel3<br>36 = TimeChannel4<br>37 = TimeChannel5<br>38 = Humidity start<br>39 = Extra unit start<br>40 = Heat/Cool step 1<br>41 = Heat/Cool step 2<br>42 = Heat/Cool step 3 |
| Ventilation1.Cor_Do2 | X,4 | 65 | | Connected signal on DO2:<br>(See signal list for DO1) |
| Ventilation1.Cor_Do3 | X,4 | 66 | | Connected signal on DO3:<br>(See signal list for DO1) |
| Ventilation1.Cor_Do4 | X,4 | 67 | | Connected signal on DO4:<br>(See signal list for DO1) |
| Ventilation1.Cor_Do5 | X,4 | 68 | | Connected signal on DO5:<br>(See signal list for DO1) |
| Ventilation1.Cor_Do6 | X,4 | 69 | | Connected signal on DO6:<br>(See signal list for DO1) |
| Ventilation1.Cor_Do7 | X,4 | 70 | | Connected signal on DO7:<br>(See signal list for DO1) |

# 4. Time Settings

## 4.1. Timer Normal Speed

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| TimeDp.Posts(0).T1 | R,3 | 40 | 7 | Start time period 1 Monday normal speed (HH.MM) |
| TimeDp.Posts(0).T2 | R,3 | 41 | 16 | Stop time period 1 Monday normal speed |
| TimeDp.Posts(0).T3 | R,3 | 42 | 0 | Start time period 2 Monday normal speed |
| TimeDp.Posts(0).T4 | R,3 | 43 | 0 | Stop time period 2 Monday normal speed |
| TimeDp.Posts(1).T1 | R,3 | 44 | 7 | Start time period 1 Tuesday normal speed |
| TimeDp.Posts(1).T2 | R,3 | 45 | 16 | Stop time period 1 Tuesday normal speed |
| TimeDp.Posts(1).T3 | R,3 | 46 | 0 | Start time period 2 Tuesday normal speed |
| TimeDp.Posts(1).T4 | R,3 | 47 | 0 | Stop time period 2 Tuesday normal speed |
| TimeDp.Posts(2).T1 | R,3 | 48 | 7 | Start time period 1 Wedn. normal speed |
| TimeDp.Posts(2).T2 | R,3 | 49 | 16 | Stop time period 1 Wedn. normal speed |
| TimeDp.Posts(2).T3 | R,3 | 50 | 0 | Start time period 2 Wedn. normal speed |
| TimeDp.Posts(2).T4 | R,3 | 51 | 0 | Stop time period 2 Wedn. normal speed |
| TimeDp.Posts(3).T1 | R,3 | 52 | 7 | Start time period 1 Thursday normal speed |
| TimeDp.Posts(3).T2 | R,3 | 53 | 16 | Stop time period 1 Thursday normal speed |
| TimeDp.Posts(3).T3 | R,3 | 54 | 0 | Start time period 2 Thursday normal speed |
| TimeDp.Posts(3).T4 | R,3 | 55 | 0 | Stop time period 2 Thursday normal speed |
| TimeDp.Posts(4).T1 | R,3 | 56 | 7 | Start time period 1 Friday normal speed |
| TimeDp.Posts(4).T2 | R,3 | 57 | 16 | Stop time period 1 Friday normal speed |
| TimeDp.Posts(4).T3 | R,3 | 58 | 0 | Start time period 2 Friday normal speed |
| TimeDp.Posts(4).T4 | R,3 | 59 | 0 | Stop time period 2 Friday normal speed |
| TimeDp.Posts(5).T1 | R,3 | 60 | 0 | Start time period 1 Saturday normal speed |
| TimeDp.Posts(5).T2 | R,3 | 61 | 0 | Stop time period 1 Saturday normal speed |
| TimeDp.Posts(5).T3 | R,3 | 62 | 0 | Start time period 2 Saturday normal speed |
| TimeDp.Posts(5).T4 | R,3 | 63 | 0 | Stop time period 2 Saturday normal speed |
| TimeDp.Posts(6).T1 | R,3 | 64 | 0 | Start time period 1 Sunday normal speed |
| TimeDp.Posts(6).T2 | R,3 | 65 | 0 | Stop time period 1 Sunday normal speed |
| TimeDp.Posts(6).T3 | R,3 | 66 | 0 | Start time period 2 Sunday normal speed |

| | | | | |
|---|---|---|---|---|
| TimeDp.Posts(6).T4 | R,3 | 67 | 0 | Stop time period 2 Sunday normal speed |
| TimeDp.Posts(7).T1 | R,3 | 68 | 0 | Start time period 1 Holiday normal speed |
| TimeDp.Posts(7).T2 | R,3 | 69 | 0 | Stop time period 1 Holiday normal speed |
| TimeDp.Posts(7).T3 | R,3 | 70 | 0 | Start time period 2 Holiday normal speed |
| TimeDp.Posts(7).T4 | R,3 | 71 | 0 | Stop time period 2 Holiday normal speed |

# 4.2. Timer Reduced Speed

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| TimeDp.Posts(8).T1 | R,3 | 72 | 0 | Start time period 1 Monday reduced speed (HH.MM) |
| TimeDp.Posts(8).T2 | R,3 | 73 | 0 | Stop time period 1 Monday reduced speed |
| TimeDp.Posts(8).T3 | R,3 | 74 | 0 | Start time period 2 Monday reduced speed |
| TimeDp.Posts(8).T4 | R,3 | 75 | 0 | Stop time period 2 Monday reduced speed |
| TimeDp.Posts(9).T1 | R,3 | 76 | 0 | Start time period 1 Tuesday reduced speed |
| TimeDp.Posts(9).T2 | R,3 | 77 | 0 | Stop time period 1 Tuesday reduced speed |
| TimeDp.Posts(9).T3 | R,3 | 78 | 0 | Start time period 2 Tuesday reduced speed |
| TimeDp.Posts(9).T4 | R,3 | 79 | 0 | Stop time period 2 Tuesday reduced speed |
| TimeDp.Posts(10).T1 | R,3 | 80 | 0 | Start time period 1 Wedn. reduced speed |
| TimeDp.Posts(10).T2 | R,3 | 81 | 0 | Stop time period 1 Wedn. reduced speed |
| TimeDp.Posts(10).T3 | R,3 | 82 | 0 | Start time period 2 Wedn. reduced speed |
| TimeDp.Posts(10).T4 | R,3 | 83 | 0 | Stop time period 2 Wedn. reduced speed |
| TimeDp.Posts(11).T1 | R,3 | 84 | 0 | Start time period 1 Thursday red.speed |
| TimeDp.Posts(11).T2 | R,3 | 85 | 0 | Stop time period 1 Thursday red. speed |
| TimeDp.Posts(11).T3 | R,3 | 86 | 0 | Start time period 2 Thursday red. speed |
| TimeDp.Posts(11).T4 | R,3 | 87 | 0 | Stop time period 2 Thursday red. speed |
| TimeDp.Posts(12).T1 | R,3 | 88 | 0 | Start time period 1 Friday reduced speed |
| TimeDp.Posts(12).T2 | R,3 | 89 | 0 | Stop time period 1 Friday reduced speed |
| TimeDp.Posts(12).T3 | R,3 | 90 | 0 | Start time period 2 Friday reduced speed |
| TimeDp.Posts(12).T4 | R,3 | 91 | 0 | Stop time period 2 Friday reduced speed |
| TimeDp.Posts(13).T1 | R,3 | 92 | 0 | Start time period 1 Saturday red. speed |
| TimeDp.Posts(13).T2 | R,3 | 93 | 0 | Stop time period 1 Saturday red. speed |
| TimeDp.Posts(13).T3 | R,3 | 94 | 0 | Start time period 2 Saturday red. speed |
| TimeDp.Posts(13).T4 | R,3 | 95 | 0 | Stop time period 2 Saturday red. speed |
| TimeDp.Posts(14).T1 | R,3 | 96 | 0 | Start time period 1 Sunday reduced speed |
| TimeDp.Posts(14).T2 | R,3 | 97 | 0 | Stop time period 1 Sunday reduced speed |
| TimeDp.Posts(14).T3 | R,3 | 98 | 0 | Start time period 2 Sunday reduced speed |
| TimeDp.Posts(14).T4 | R,3 | 99 | 0 | Stop time period 2 Sunday reduced speed |
| TimeDp.Posts(15).T1 | R,3 | 100 | 0 | Start time period 1 Holiday reduced speed |
| TimeDp.Posts(15).T2 | R,3 | 101 | 0 | Stop time period 1 Holiday reduced speed |
| TimeDp.Posts(15).T3 | R,3 | 102 | 0 | Start time period 2 Holiday reduced speed |

| | | | | |
|---|---|---|---|---|
| TimeDp.Posts(15).T4 | R,3 | 103 | 0 | Stop time period 2 Holiday reduced speed |

# 4.3. Timer output 1

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| TimeDp.Posts(16).T1 | R,3 | 104 | 7 | Start time period 1 Monday timer output 1 (HH.MM) |
| TimeDp.Posts(16).T2 | R,3 | 105 | 16 | Stop time period 1 Monday timer output 1 |
| TimeDp.Posts(16).T3 | R,3 | 106 | 0 | Start time period 2 Monday timer output 1 |
| TimeDp.Posts(16).T4 | R,3 | 107 | 0 | Stop time period 2 Monday timer output 1 |
| TimeDp.Posts(17).T1 | R,3 | 108 | 7 | Start time period 1 Tuesday timer output 1 |
| TimeDp.Posts(17).T2 | R,3 | 109 | 16 | Stop time period 1 Tuesday timer output 1 |
| TimeDp.Posts(17).T3 | R,3 | 110 | 0 | Start time period 2 Tuesday timer output 1 |
| TimeDp.Posts(17).T4 | R,3 | 111 | 0 | Stop time period 2 Tuesday timer output 1 |
| TimeDp.Posts(18).T1 | R,3 | 112 | 7 | Start time period 1 Wednesd.timer output 1 |
| TimeDp.Posts(18).T2 | R,3 | 113 | 16 | Stop time period 1 Wedn. timer output 1 |
| TimeDp.Posts(18).T3 | R,3 | 114 | 0 | Start time period 2 Wedn. timer output 1 |
| TimeDp.Posts(18).T4 | R,3 | 115 | 0 | Stop time period 2 Wedn. timer output 1 |
| TimeDp.Posts(19).T1 | R,3 | 116 | 7 | Start time period 1 Thursday timer output 1 |
| TimeDp.Posts(19).T2 | R,3 | 117 | 16 | Stop time period 1 Thursday timer output 1 |
| TimeDp.Posts(19).T3 | R,3 | 118 | 0 | Start time period 2 Thursday timer output 1 |
| TimeDp.Posts(19).T4 | R,3 | 119 | 0 | Stop time period 2 Thursday timer output 1 |
| TimeDp.Posts(20).T1 | R,3 | 120 | 7 | Start time period 1 Friday timer output 1 |
| TimeDp.Posts(20).T2 | R,3 | 121 | 16 | Stop time period 1 Friday timer output 1 |
| TimeDp.Posts(20).T3 | R,3 | 122 | 0 | Start time period 2 Friday timer output 1 |
| TimeDp.Posts(20).T4 | R,3 | 123 | 0 | Stop time period 2 Friday timer output 1 |
| TimeDp.Posts(21).T1 | R,3 | 124 | 0 | Start time period 1 Saturday timer output 1 |
| TimeDp.Posts(21).T2 | R,3 | 125 | 0 | Stop time period 1 Saturday timer output 1 |
| TimeDp.Posts(21).T3 | R,3 | 126 | 0 | Start time period 2 Saturday timer output 1 |
| TimeDp.Posts(21).T4 | R,3 | 127 | 0 | Stop time period 2 Saturday timer output 1 |
| TimeDp.Posts(22).T1 | R,3 | 128 | 0 | Start time period 1 Sunday timer output 1 |
| TimeDp.Posts(22).T2 | R,3 | 129 | 0 | Stop time period 1 Sunday timer output 1 |
| TimeDp.Posts(22).T3 | R,3 | 130 | 0 | Start time period 2 Sunday timer output 1 |
| TimeDp.Posts(22).T4 | R,3 | 131 | 0 | Stop time period 2 Sunday timer output 1 |
| TimeDp.Posts(23).T1 | R,3 | 132 | 0 | Start time period 1 Holiday timer output 1 |
| TimeDp.Posts(23).T2 | R,3 | 133 | 0 | Stop time period 1 Holiday timer output 1 |
| TimeDp.Posts(23).T3 | R,3 | 134 | 0 | Start time period 2 Holiday timer output 1 |
| TimeDp.Posts(23).T4 | R,3 | 135 | 0 | Stop time period 2 Holiday timer output 1 |

# 4.4. Timer output 2

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| TimeDp.Posts(24).T1 | R,3 | 136 | 7 | Start time period 1 Monday timer output 2 (HH.MM) |
| TimeDp.Posts(24).T2 | R,3 | 137 | 16 | Stop time period 1 Monday timer output 2 |
| TimeDp.Posts(24).T3 | R,3 | 138 | 0 | Start time period 2 Monday timer output 2 |
| TimeDp.Posts(24).T4 | R,3 | 139 | 0 | Stop time period 2 Monday timer output 2 |
| TimeDp.Posts(25).T1 | R,3 | 140 | 7 | Start time period 1 Tuesday timer output 2 |
| TimeDp.Posts(25).T2 | R,3 | 141 | 16 | Stop time period 1 Tuesday timer output 2 |
| TimeDp.Posts(25).T3 | R,3 | 142 | 0 | Start time period 2 Tuesday timer output 2 |
| TimeDp.Posts(25).T4 | R,3 | 143 | 0 | Stop time period 2 Tuesday timer output 2 |
| TimeDp.Posts(26).T1 | R,3 | 144 | 7 | Start time period 1 Wedn. timer output 2 |
| TimeDp.Posts(26).T2 | R,3 | 145 | 16 | Stop time period 1 Wedn. timer output 2 |
| TimeDp.Posts(26).T3 | R,3 | 146 | 0 | Start time period 2 Wedn. timer output 2 |
| TimeDp.Posts(26).T4 | R,3 | 147 | 0 | Stop time period 2 Wedn. timer output 2 |
| TimeDp.Posts(27).T1 | R,3 | 148 | 7 | Start time period 1 Thursday timer output 2 |
| TimeDp.Posts(27).T2 | R,3 | 149 | 16 | Stop time period 1 Thursday timer output 2 |
| TimeDp.Posts(27).T3 | R,3 | 150 | 0 | Start time period 2 Thursday timer output 2 |
| TimeDp.Posts(27).T4 | R,3 | 151 | 0 | Stop time period 2 Thursday timer output 2 |
| TimeDp.Posts(28).T1 | R,3 | 152 | 7 | Start time period 1 Friday timer output 2 |
| TimeDp.Posts(28).T2 | R,3 | 153 | 16 | Stop time period 1 Friday timer output 2 |
| TimeDp.Posts(28).T3 | R,3 | 154 | 0 | Start time period 2 Friday timer output 2 |
| TimeDp.Posts(28).T4 | R,3 | 155 | 0 | Stop time period 2 Friday timer output 2 |
| TimeDp.Posts(29).T1 | R,3 | 156 | 0 | Start time period 1 Saturday timer output 2 |
| TimeDp.Posts(29).T2 | R,3 | 157 | 0 | Stop time period 1 Saturday timer output 2 |
| TimeDp.Posts(29).T3 | R,3 | 158 | 0 | Start time period 2 Saturday timer output 2 |
| TimeDp.Posts(29).T4 | R,3 | 159 | 0 | Stop time period 2 Saturday timer output 2 |
| TimeDp.Posts(30).T1 | R,3 | 160 | 0 | Start time period 1 Sunday timer output 2 |
| TimeDp.Posts(30).T2 | R,3 | 161 | 0 | Stop time period 1 Sunday timer output 2 |
| TimeDp.Posts(30).T3 | R,3 | 162 | 0 | Start time period 2 Sunday timer output 2 |
| TimeDp.Posts(30).T4 | R,3 | 163 | 0 | Stop time period 2 Sunday timer output 2 |
| TimeDp.Posts(31).T1 | R,3 | 164 | 0 | Start time period 1 Holiday timer output 2 |
| TimeDp.Posts(31).T2 | R,3 | 165 | 0 | Stop time period 1 Holiday timer output 2 |
| TimeDp.Posts(31).T3 | R,3 | 166 | 0 | Start time period 2 Holiday timer output 2 |
| TimeDp.Posts(31).T4 | R,3 | 167 | 0 | Stop time period 2 Holiday timer output 2 |

# 4.5. Timer output 3

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| TimeDp.Posts(32).T1 | R,3 | 168 | 7 | Start time period 1 Monday timer output 3 (HH.MM) |
| TimeDp.Posts(32).T2 | R,3 | 169 | 16 | Stop time period 1 Monday timer output 3 |
| TimeDp.Posts(32).T3 | R,3 | 170 | 0 | Start time period 2 Monday timer output 3 |
| TimeDp.Posts(32).T4 | R,3 | 171 | 0 | Stop time period 2 Monday timer output 3 |
| TimeDp.Posts(33).T1 | R,3 | 172 | 7 | Start time period 1 Tuesday timer output 3 |
| TimeDp.Posts(33).T2 | R,3 | 173 | 16 | Stop time period 1 Tuesday timer output 3 |
| TimeDp.Posts(33).T3 | R,3 | 174 | 0 | Start time period 2 Tuesday timer output 3 |
| TimeDp.Posts(33).T4 | R,3 | 175 | 0 | Stop time period 2 Tuesday timer output 3 |
| TimeDp.Posts(34).T1 | R,3 | 176 | 7 | Start time period 1 Wedn. timer output 3 |
| TimeDp.Posts(34).T2 | R,3 | 177 | 16 | Stop time period 1 Wedn. timer output 3 |
| TimeDp.Posts(34).T3 | R,3 | 178 | 0 | Start time period 2 Wedn. timer output 3 |
| TimeDp.Posts(34).T4 | R,3 | 179 | 0 | Stop time period 2 Wedn. timer output 3 |
| TimeDp.Posts(35).T1 | R,3 | 180 | 7 | Start time period 1 Thursday timer output 3 |
| TimeDp.Posts(35).T2 | R,3 | 181 | 16 | Stop time period 1 Thursday timer output 3 |
| TimeDp.Posts(35).T3 | R,3 | 182 | 0 | Start time period 2 Thursday timer output 3 |
| TimeDp.Posts(35).T4 | R,3 | 183 | 0 | Stop time period 2 Thursday timer output 3 |
| TimeDp.Posts(36).T1 | R,3 | 184 | 7 | Start time period 1 Friday timer output 3 |
| TimeDp.Posts(36).T2 | R,3 | 185 | 16 | Stop time period 1 Friday timer output 3 |
| TimeDp.Posts(36).T3 | R,3 | 186 | 0 | Start time period 2 Friday timer output 3 |
| TimeDp.Posts(36).T4 | R,3 | 187 | 0 | Stop time period 2 Friday timer output 3 |
| TimeDp.Posts(37).T1 | R,3 | 188 | 0 | Start time period 1 Saturday timer output 3 |
| TimeDp.Posts(37).T2 | R,3 | 189 | 0 | Stop time period 1 Saturday timer output 3 |
| TimeDp.Posts(37).T3 | R,3 | 190 | 0 | Start time period 2 Saturday timer output 3 |
| TimeDp.Posts(37).T4 | R,3 | 191 | 0 | Stop time period 2 Saturday timer output 3 |
| TimeDp.Posts(38).T1 | R,3 | 192 | 0 | Start time period 1 Sunday timer output 3 |
| TimeDp.Posts(38).T2 | R,3 | 193 | 0 | Stop time period 1 Sunday timer output 3 |
| TimeDp.Posts(38).T3 | R,3 | 194 | 0 | Start time period 2 Sunday timer output 3 |
| TimeDp.Posts(38).T4 | R,3 | 195 | 0 | Stop time period 2 Sunday timer output 3 |
| TimeDp.Posts(39).T1 | R,3 | 196 | 0 | Start time period 1 Holiday timer output 3 |
| TimeDp.Posts(39).T2 | R,3 | 197 | 0 | Stop time period 1 Holiday timer output 3 |
| TimeDp.Posts(39).T3 | R,3 | 198 | 0 | Start time period 2 Holiday timer output 3 |
| TimeDp.Posts(39).T4 | R,3 | 199 | 0 | Stop time period 2 Holiday timer output 3 |

# 4.6. Timer output 4

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| TimeDp.Posts(40).T1 | R,3 | 200 | 7 | Start time period 1 Monday timer output 4 (HH.MM) |
| TimeDp.Posts(40).T2 | R,3 | 201 | 16 | Stop time period 1 Monday timer output 4 |
| TimeDp.Posts(40).T3 | R,3 | 202 | 0 | Start time period 2 Monday timer output 4 |
| TimeDp.Posts(40).T4 | R,3 | 203 | 0 | Stop time period 2 Monday timer output 4 |
| TimeDp.Posts(41).T1 | R,3 | 204 | 7 | Start time period 1 Tuesday timer output 4 |
| TimeDp.Posts(41).T2 | R,3 | 205 | 16 | Stop time period 1 Tuesday timer output 4 |
| TimeDp.Posts(41).T3 | R,3 | 206 | 0 | Start time period 2 Tuesday timer output 4 |
| TimeDp.Posts(41).T4 | R,3 | 207 | 0 | Stop time period 2 Tuesday timer output 4 |
| TimeDp.Posts(42).T1 | R,3 | 208 | 7 | Start time period 1 Wedn. timer output 4 |
| TimeDp.Posts(42).T2 | R,3 | 209 | 16 | Stop time period 1 Wedn. timer output 4 |
| TimeDp.Posts(42).T3 | R,3 | 210 | 0 | Start time period 2 Wedn. timer output 4 |
| TimeDp.Posts(42).T4 | R,3 | 211 | 0 | Stop time period 2 Wedn. timer output 4 |
| TimeDp.Posts(43).T1 | R,3 | 212 | 7 | Start time period 1 Thursday timer output 4 |
| TimeDp.Posts(43).T2 | R,3 | 213 | 16 | Stop time period 1 Thursday timer output 4 |
| TimeDp.Posts(43).T3 | R,3 | 214 | 0 | Start time period 2 Thursday timer output 4 |
| TimeDp.Posts(43).T4 | R,3 | 215 | 0 | Stop time period 2 Thursday timer output 4 |
| TimeDp.Posts(44).T1 | R,3 | 216 | 7 | Start time period 1 Friday timer output 4 |
| TimeDp.Posts(44).T2 | R,3 | 217 | 16 | Stop time period 1 Friday timer output 4 |
| TimeDp.Posts(44).T3 | R,3 | 218 | 0 | Start time period 2 Friday timer output 4 |
| TimeDp.Posts(44).T4 | R,3 | 219 | 0 | Stop time period 2 Friday timer output 4 |
| TimeDp.Posts(45).T1 | R,3 | 220 | 0 | Start time period 1 Saturday timer output 4 |
| TimeDp.Posts(45).T2 | R,3 | 221 | 0 | Stop time period 1 Saturday timer output 4 |
| TimeDp.Posts(45).T3 | R,3 | 222 | 0 | Start time period 2 Saturday timer output 4 |
| TimeDp.Posts(45).T4 | R,3 | 223 | 0 | Stop time period 2 Saturday timer output 4 |
| TimeDp.Posts(46).T1 | R,3 | 224 | 0 | Start time period 1 Sunday timer output 4 |
| TimeDp.Posts(46).T2 | R,3 | 225 | 0 | Stop time period 1 Sunday timer output 4 |
| TimeDp.Posts(46).T3 | R,3 | 226 | 0 | Start time period 2 Sunday timer output 4 |
| TimeDp.Posts(46).T4 | R,3 | 227 | 0 | Stop time period 2 Sunday timer output 4 |
| TimeDp.Posts(47).T1 | R,3 | 228 | 0 | Start time period 1 Holiday timer output 4 |
| TimeDp.Posts(47).T2 | R,3 | 229 | 0 | Stop time period 1 Holiday timer output 4 |
| TimeDp.Posts(47).T3 | R,3 | 230 | 0 | Start time period 2 Holiday timer output 4 |
| TimeDp.Posts(47).T4 | R,3 | 231 | 0 | Stop time period 2 Holiday timer output 4 |

# 4.7. Timer output 5

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| TimeDp.Posts(48).T1 | R,3 | 232 | 7 | Start time period 1 Monday timer output 5 (HH.MM) |
| TimeDp.Posts(48).T2 | R,3 | 233 | 16 | Stop time period 1 Monday timer output 5 |
| TimeDp.Posts(48).T3 | R,3 | 234 | 0 | Start time period 2 Monday timer output 5 |
| TimeDp.Posts(48).T4 | R,3 | 235 | 0 | Stop time period 2 Monday timer output 5 |
| TimeDp.Posts(49).T1 | R,3 | 236 | 7 | Start time period 1 Tuesday timer output 5 |
| TimeDp.Posts(49).T2 | R,3 | 237 | 16 | Stop time period 1 Tuesday timer output 5 |
| TimeDp.Posts(49).T3 | R,3 | 238 | 0 | Start time period 2 Tuesday timer output 5 |
| TimeDp.Posts(49).T4 | R,3 | 239 | 0 | Stop time period 2 Tuesday timer output 5 |
| TimeDp.Posts(50).T1 | R,3 | 240 | 7 | Start time period 1 Wedn. timer output 5 |
| TimeDp.Posts(50).T2 | R,3 | 241 | 16 | Stop time period 1 Wedn. timer output 5 |
| TimeDp.Posts(50).T3 | R,3 | 242 | 0 | Start time period 2 Wedn. timer output 5 |
| TimeDp.Posts(50).T4 | R,3 | 243 | 0 | Stop time period 2 Wedn. timer output 5 |
| TimeDp.Posts(51).T1 | R,3 | 244 | 7 | Start time period 1 Thursday timer output 5 |
| TimeDp.Posts(51).T2 | R,3 | 245 | 16 | Stop time period 1 Thursday timer output 5 |
| TimeDp.Posts(51).T3 | R,3 | 246 | 0 | Start time period 2 Thursday timer output 5 |
| TimeDp.Posts(51).T4 | R,3 | 247 | 0 | Stop time period 2 Thursday timer output 5 |
| TimeDp.Posts(52).T1 | R,3 | 248 | 7 | Start time period 1 Friday timer output 5 |
| TimeDp.Posts(52).T2 | R,3 | 249 | 16 | Stop time period 1 Friday timer output 5 |
| TimeDp.Posts(52).T3 | R,3 | 250 | 0 | Start time period 2 Friday timer output 5 |
| TimeDp.Posts(52).T4 | R,3 | 251 | 0 | Stop time period 2 Friday timer output 5 |
| TimeDp.Posts(53).T1 | R,3 | 252 | 0 | Start time period 1 Saturday timer output 5 |
| TimeDp.Posts(53).T2 | R,3 | 253 | 0 | Stop time period 1 Saturday timer output 5 |
| TimeDp.Posts(53).T3 | R,3 | 254 | 0 | Start time period 2 Saturday timer output 5 |
| TimeDp.Posts(53).T4 | R,3 | 255 | 0 | Stop time period 2 Saturday timer output 5 |
| TimeDp.Posts(54).T1 | R,3 | 256 | 0 | Start time period 1 Sunday timer output 5 |
| TimeDp.Posts(54).T2 | R,3 | 257 | 0 | Stop time period 1 Sunday timer output 5 |
| TimeDp.Posts(54).T3 | R,3 | 258 | 0 | Start time period 2 Sunday timer output 5 |
| TimeDp.Posts(54).T4 | R,3 | 259 | 0 | Stop time period 2 Sunday timer output 5 |
| TimeDp.Posts(55).T1 | R,3 | 260 | 0 | Start time period 1 Holiday timer output 5 |
| TimeDp.Posts(55).T2 | R,3 | 261 | 0 | Stop time period 1 Holiday timer output 5 |
| TimeDp.Posts(55).T3 | R,3 | 262 | 0 | Start time period 2 Holiday timer output 5 |
| TimeDp.Posts(55).T4 | R,3 | 263 | 0 | Stop time period 2 Holiday timer output 5 |

# 4.8. Holidays

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| TimeHp.Posts(0).FromDate | R,3 | 264 | 01.01 | Start date holiday period 1 (MM.DD) |
| TimeHp.Posts(0).ToDate | R,3 | 265 | 01.01 | End date holiday period 1 (MM.DD) |
| TimeHp.Posts(1).FromDate | R,3 | 266 | 01.01 | Start date holiday period 2 (MM.DD) |
| TimeHp.Posts(1).ToDate | R,3 | 267 | 01.01 | End date holiday period 2 (MM.DD) |
| TimeHp.Posts(2).FromDate | R,3 | 268 | 01.01 | Start date holiday period 3 (MM.DD) |
| TimeHp.Posts(2).ToDate | R,3 | 269 | 01.01 | End date holiday period 3 (MM.DD) |
| TimeHp.Posts(3).FromDate | R,3 | 270 | 01.01 | Start date holiday period 4 (MM.DD) |
| TimeHp.Posts(3).ToDate | R,3 | 271 | 01.01 | End date holiday period 4 (MM.DD) |
| TimeHp.Posts(4).FromDate | R,3 | 272 | 01.01 | Start date holiday period 5 (MM.DD) |
| TimeHp.Posts(4).ToDate | R,3 | 273 | 01.01 | End date holiday period 5 (MM.DD) |
| TimeHp.Posts(5).FromDate | R,3 | 274 | 01.01 | Start date holiday period 6 (MM.DD) |
| TimeHp.Posts(5).ToDate | R,3 | 275 | 01.01 | End date holiday period 6 (MM.DD) |
| TimeHp.Posts(6).FromDate | R,3 | 276 | 01.01 | Start date holiday period 7 (MM.DD) |
| TimeHp.Posts(6).ToDate | R,3 | 277 | 01.01 | End date holiday period 7 (MM.DD) |
| TimeHp.Posts(7).FromDate | R,3 | 278 | 01.01 | Start date holiday period 8 (MM.DD) |
| TimeHp.Posts(7).ToDate | R,3 | 279 | 01.01 | End date holiday period 8 (MM.DD) |
| TimeHp.Posts(8).FromDate | R,3 | 280 | 01.01 | Start date holiday period 9 (MM.DD) |
| TimeHp.Posts(8).ToDate | R,3 | 281 | 01.01 | End date holiday period 9 (MM.DD) |
| TimeHp.Posts(9).FromDate | R,3 | 282 | 01.01 | Start date holiday period 10 (MM.DD) |
| TimeHp.Posts(9).ToDate | R,3 | 283 | 01.01 | End date holiday period 10 (MM.DD) |
| TimeHp.Posts(10).FromDate | R,3 | 284 | 01.01 | Start date holiday period 11 (MM.DD) |
| TimeHp.Posts(10).ToDate | R,3 | 285 | 01.01 | End date holiday period 11 (MM.DD) |
| TimeHp.Posts(11).FromDate | R,3 | 286 | 01.01 | Start date holiday period 12 (MM.DD) |
| TimeHp.Posts(11).ToDate | R,3 | 287 | 01.01 | End date holiday period 12 (MM.DD) |
| TimeHp.Posts(12).FromDate | R,3 | 288 | 01.01 | Start date holiday period 13 (MM.DD) |
| TimeHp.Posts(12).ToDate | R,3 | 289 | 01.01 | End date holiday period 13 (MM.DD) |
| TimeHp.Posts(13).FromDate | R,3 | 290 | 01.01 | Start date holiday period 14 (MM.DD) |
| TimeHp.Posts(13).ToDate | R,3 | 291 | 01.01 | End date holiday period 14 (MM.DD) |
| TimeHp.Posts(14).FromDate | R,3 | 292 | 01.01 | Start date holiday period 15 (MM.DD) |
| TimeHp.Posts(14).ToDate | R,3 | 293 | 01.01 | End date holiday period 15 (MM.DD) |
| TimeHp.Posts(15).FromDate | R,3 | 294 | 01.01 | Start date holiday period 16 (MM.DD) |
| TimeHp.Posts(15).ToDate | R,3 | 295 | 01.01 | End date holiday period 16 (MM.DD) |
| TimeHp.Posts(16).FromDate | R,3 | 296 | 01.01 | Start date holiday period 17 (MM.DD) |

| | | | | |
|---|---|---|---|---|
| TimeHp.Posts(16).ToDate | R,3 | 297 | 01.01 | End date holiday period 17 (MM.DD) |
| TimeHp.Posts(17).FromDate | R,3 | 298 | 01.01 | Start date holiday period 18 (MM.DD) |
| TimeHp.Posts(17).ToDate | R,3 | 299 | 01.01 | End date holiday period 18 (MM.DD) |
| TimeHp.Posts(18).FromDate | R,3 | 300 | 01.01 | Start date holiday period 19 (MM.DD) |
| TimeHp.Posts(18).ToDate | R,3 | 301 | 01.01 | End date holiday period 19 (MM.DD) |
| TimeHp.Posts(19).FromDate | R,3 | 302 | 01.01 | Start date holiday period 20 (MM.DD) |
| TimeHp.Posts(19).ToDate | R,3 | 303 | 01.01 | End date holiday period 20 (MM.DD) |
| TimeHp.Posts(20).FromDate | R,3 | 304 | 01.01 | Start date holiday period 21 (MM.DD) |
| TimeHp.Posts(20).ToDate | R,3 | 305 | 01.01 | End date holiday period 21 (MM.DD) |
| TimeHp.Posts(21).FromDate | R,3 | 306 | 01.01 | Start date holiday period 22 (MM.DD) |
| TimeHp.Posts(21).ToDate | R,3 | 307 | 01.01 | End date holiday period 22 (MM.DD) |
| TimeHp.Posts(22).FromDate | R,3 | 308 | 01.01 | Start date holiday period 23 (MM.DD) |
| TimeHp.Posts(22).ToDate | R,3 | 309 | 01.01 | End date holiday period 23 (MM.DD) |
| TimeHp.Posts(23).FromDate | R,3 | 310 | 01.01 | Start date holiday period 24 (MM.DD) |
| TimeHp.Posts(23).ToDate | R,3 | 311 | 01.01 | End date holiday period 24 (MM.DD) |

# 4.9. Real Time Clock

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| QSystem.Sec | X,3 | 406 | | Real time clock: Second 0-59 |
| QSystem.Minute | X,3 | 407 | | Real time clock: Minute 0-59 |
| QSystem.Hour | X,3 | 408 | | Real time clock: Hour 0-23 |
| QSystem.WDay | X,3 | 409 | | Real time clock: Day of Week 1-7, 1=Monday |
| QSystem.Week | X,3 | 410 | | Real time clock: Week number 1-53 |
| QSystem.Date | X,3 | 411 | | Real time clock: Day of month 1-31 |
| QSystem.Month | X,3 | 412 | | Real time clock: Month 1-12 |
| QSystem.Year | X,3 | 413 | | Real time clock: Year 0-99 |

# 5. Settings

## 5.1. General

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation1.Cor_OverHeatFastStop | L,1 | 1 | 0 | Enable fast stop on overheat alarm |
| Ventilation1.Cor_CoolStepAlarmBlock | L,1 | 2 | 0 | If set, block cooling step signals on alarm "Run Error P1-Cooler" |
| Ventilation1.Cor_AlaAcknowAll | L,1 | 3 | 0 | Command to acknowledge all alarms |
| Ventilation1.Cor_ReservedL | L,1 | 7 | 0 | Not used |
| Ventilation1.Cor_ReservedL | L,1 | 8 | 0 | Not used |
| Ventilation1.Cor_ReservedL | L,1 | 9 | 0 | Not used |
| Ventilation1.Cor_ReservedL | L,1 | 10 | 0 | Not used |
| Ventilation1.Cor_ReservedL | L,1 | 11 | 0 | Not used |
| Ventilation1.Cor_ReservedL | L,1 | 12 | 0 | Not used |
| Ventilation1.Cor_ReservedL | L,1 | 13 | 0 | Not used |
| Ventilation1.Cor_ReservedL | L,1 | 14 | 0 | Not used |
| Ventilation1.Cor_ReservedL | L,1 | 15 | 0 | Not used |
| Ventilation1.Cor_ReservedL | L,1 | 16 | 0 | Not used |
| Ventilation1.Cor_ExchStartDelay | I,3 | 422 | 0 sec | Start delay Exchanger (sec) |
| Ventilation1.Cor_DXBlockLimit | R,3 | 423 | 0 ℃ | If lowe r outdoor temperature all DX-cooling steps are blocked |
| Ventilation1.Cor_CoolStepBlock1 | R,3 | 428 | 0 % | If frequency output signal SAF is lower, Cool step 1 is blocked |
| Ventilation1.Cor_CoolStepBlock2 | R,3 | 429 | 0 % | If frequency output signal SAF is lower, Cool step 2 is blocked |
| Ventilation1.Cor_CoolStepBlock3 | R,3 | 430 | 0 % | If frequency output signal SAF is lower, Cool step 3 is blocked |
| Ventilation1.Cor_CoolStepBlockLimit1 (0) | R,3 | 431 | 13 ℃ | If lower outdoor temperature Cool ste p 1 is blocked |
| Ventilation1.Cor_CoolStepBlockLimit2 | R,3 | 432 | 13 ℃ | If lower outdoor temperature Cool ste p 2 is blocked |
| Ventilation1.Cor_CoolStepBlockLimit3 | R,3 | 433 | 13 ℃ | If lower outdoor temperature Cool ste p 3 is blocked |

## 5.2. Control temp

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation4.Cor_SupplyPID_PGain | R,3 | 312 | 33 ℃ | P-ba nd supply air control |
| Ventilation4.Cor_SupplyPID_ITime | R,3 | 313 | 100 sec | I-time supply air control |
| Ventilation4.Cor_ExhaustPID_PGain | R,3 | 314 | 100 ℃ | P- band exhaust air control |
| Ventilation4.Cor_ExhaustPID_ITime | R,3 | 315 | 300 sec | I-time exhaust air control |
| Ventilation4.Cor_RoomPID_PGain | R,3 | 316 | 100 ℃ | P-ban d room air control |
| Ventilation4.Cor_RoomPID_ITime | R,3 | 317 | 300 sec | I-time room air control |
| Ventilation4.Cor_FrostPID_PGain | R,3 | 318 | 100 ℃ | P-ba nd switchdown mode |
| Ventilation4.Cor_FrostPID_ITime | R,3 | 319 | 100 sec | I-time switchdown mode |
| Ventilation4.Cor_DeIcePID_PGain | R,3 | 320 | 100 ℃ | P-ba nd de-icing |
| Ventilation4.Cor_DeIcePID_ITime | R,3 | 321 | 100 sec | I-time de-icing |

## 5.3. Control pressure

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation4.Cor_SAFPID_PGain | R,3 | 322 | 500 Pa | P-band pressure control SAF |
| Ventilation4.Cor_SAFPID_ITime | R,3 | 323 | 60 sec | I-time pressure control SAF |
| Ventilation4.Cor_EAFPID_PGain | R,3 | 324 | 500 Pa | P-band pressure control EAF |
| Ventilation4.Cor_EAFPID_ITime | R,3 | 325 | 60 sec | I-time pressure control EAF |

## 5.4. Control flow

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation1.Cor_SAFAirFlowPID_PG ain | R,3 | 326 | 1000 m3/h | P-band flow control SAF |
| Ventilation4.Cor_SAFPID_ITime | R,3 | 327 | 60 sec | I-time flow control SAF |
| Ventilation1.Cor_EAFAirFlowPID_PG ain | R,3 | 328 | 1000 m3/h | P-band flow control EAF |
| Ventilation4.Cor_EAFPID_ITime | R,3 | 329 | 60 sec | I-time flow control EAF |

## 5.5. Control humidity

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation4.Cor_HumidityPID_PGain | R,3 | 330 | 100 %RH | P-band humidity control |
| Ventilation4.Cor_HumidityPID_ITime | R,3 | 331 | 300 sec | I-time humidity control |

## 5.6. Alarm limits

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation1.Cor_SupplyMaxDiff | R,3 | 332 | 10 ℃ | Max co ntrol deviation supply air temp |
| Ventilation1.Cor_SupplyHighAlarmLimit | R,3 | 333 | 30 ℃ | High alarm limit supply air temp |
| Ventilation1.Cor_SupplyLowAlarmLimit | R,3 | 334 | 10 ℃ | Low alarm limit supply air temp |
| Ventilation1.Cor_ExhaustAirTempHigh | R,3 | 335 | 30 ℃ | High alarm limit exhaust air temp |
| Ventilation1.Cor_ExhaustAirTempLow | R,3 | 336 | 10 ℃ | Low alarm limit exhaust air temp |
| Ventilation1.Cor_RoomHighLimit | R,3 | 337 | 30 ℃ | High a larm limit room air temp |
| Ventilation1.Cor_RoomLowLimit | R,3 | 338 | 10 ℃ | Low ala rm limit room air temp |
| Ventilation1.Cor_FrostLimit | R,3 | 339 | 7 ℃ | Alarm limi t frost protection |
| Ventilation1.Cor_SAFMaxDiffPressure | R,3 | 340 | 50 Pa | Max control deviation pressure SAF |
| Ventilation1.Cor_EAFMaxDiffPressure | R,3 | 341 | 50 Pa | Max control deviation pressure EAF |
| Ventilation1.Cor_EfficiencyLowLimit | R,3 | 342 | 50 % | Low efficiency |

## 5.7. Alarm delays

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| AlaData.AlaPt13_DelayValue | I,3 | 343 | 30 min | Alarm delay control deviation supply air temp |
| AlaData.AlaPt15_DelayValue | I,3 | 344 | 5 sec | Alarm delay high supply air temp |
| AlaData.AlaPt16_DelayValue | I,3 | 345 | 5 sec | Alarm delay low supply air temp |
| AlaData.AlaPt21_DelayValue | I,3 | 346 | 30 min | Alarm delay high exhaust air temp |
| AlaData.AlaPt22_DelayValue | I,3 | 347 | 30 min | Alarm delay low exhaust air temp |
| AlaData.AlaPt19_DelayValue | I,3 | 348 | 30 min | Alarm delay high room air temp |
| AlaData.AlaPt20_DelayValue | I,3 | 349 | 30 min | Alarm delay low alarm room air temp |

| | | | | |
|---|---|---|---|---|
| AlaData.AlaPt25_DelayValue | I,3 | 350 | 0 sec | Alarm delay frost protection |
| AlaData.AlaPt31_DelayValue | I,3 | 351 | 30 min | Alarm delay max control deviation pressure SAF |
| AlaData.AlaPt32_DelayValue | I,3 | 352 | 30 min | Alarm delay max control deviation pressure EAF |
| AlaData.AlaPt26_DelayValue | I,3 | 353 | 30 min | Alarm delay low efficiency |
| AlaData.AlaPt1_DelayValue | I,3 | 354 | 120 sec | Alarm delay malfunction SAF |
| AlaData.AlaPt2_DelayValue | I,3 | 355 | 120 sec | Alarm delay malfunction EAF |
| AlaData.AlaPt3_DelayValue | I,3 | 356 | 5 sec | Alarm delay malfunction P1-Heating |
| AlaData.AlaPt4_DelayValue | I,3 | 357 | 5 sec | Alarm delay malfunction P1-Cooling |
| AlaData.AlaPt5_DelayValue | I,3 | 358 | 20 sec | Alarm delay malfunction P1-Exchanger |
| AlaData.AlaPt6_DelayValue | I,3 | 359 | 180 sec | Alarm delay filter monitoring |
| AlaData.AlaPt7_DelayValue | I,3 | 360 | 5 sec | Alarm delay flow switch |
| AlaData.AlaPt8_DelayValue | I,3 | 361 | 0 sec | Alarm delay frost protection |
| AlaData.AlaPt9_DelayValue | I,3 | 362 | 0 sec | Alarm delay frost protection digital input |
| AlaData.AlaPt10_DelayValue | I,3 | 363 | 0 sec | Alarm delay fire alarm |
| AlaData.AlaPt12_DelayValue | I,3 | 364 | 0 sec | Alarm delay external alarm |
| AlaData.AlaPt23_DelayValue | I,3 | 365 | 0 sec | Alarm delay electric heater |
| AlaData.AlaPt27_DelayValue | I,3 | 366 | 5 sec | Alarm delay sensor error |
| AlaData.AlaPt29_DelayValue | I,3 | 367 | 20 sec | Alarm delay rotation guard exchanger |

# 6. Manual/Auto

## 6.1. Manual/Auto

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation1.Cor_VentAutoMode | X,3 | 368 | 2 | Running mode air unit:<br>0=Manual off<br>1=Manual on<br>2=Auto |
| Ventilation4.Cor_SupplyPID_Select | X,3 | 369 | 2 | Supply temp controller mode:<br>0=Manual off<br>1=Manual on<br>2=Auto |
| Ventilation4.Cor_SupplyPID_ManSet | R,3 | 370 | 0 % | Supply temp controller output if manual on mode |
| Ventilation1.Cor_SAFAutoMode(0) | X,3 | 371 | 3 | Running mode SAF:<br>0=Off<br>1=Manual half speed<br>2=Manual full speed<br>3=Auto |
| Ventilation1.Cor_EAFAutoMode | X,3 | 372 | 3 | Running mode EAF:<br>0=Off<br>1=Manual half speed<br>2=Manual full speed<br>3=Auto |
| Ventilation1.Cor_SAFFrequenceAuto Mode | X,3 | 373 | 3 | Running mode frequence controlled SAF<br>0=Manual<br>1=Man. half speed<br>2=Man. Fullspeed<br>3=Auto |
| Ventilation1.Cor_SAFManual | R,3 | 374 | 0 % | Freguencer controller output SAF if manual mode |
| Ventilation1.Cor_EAFFrequenceAuto Mode | X,3 | 375 | 3 | Running mode frequence controlled EAF<br>0=Manual<br>1=Man. half speed<br>2=Man. Fullspeed<br>3=Auto |
| Ventilation1.Cor_EAFManual | R,3 | 376 | 0 % | Freguencer controller output EAF if manual mode |

| | | | | |
|---|---|---|---|---|
| Ventilation1.Cor_HeatCoilAutoMode(0) | X,3 | 377 | 2 | Running mode Heating:<br>0=Off<br>1=Manual<br>2=Auto |
| Ventilation1.Cor_HeatCoilManual(0) | R,3 | 378 | 0 | Heating controller output if manual mode |
| Ventilation1.Cor_ExchCoilAutoMode | X,3 | 379 | 2 | Running mode Exchanger:<br>0=Off<br>1=Manual<br>2=Auto |
| Ventilation1.Cor_ExchCoilManual | R,3 | 380 | 0 | Exchanger controller output if manual mode |
| Ventilation1.Cor_CoolCoilAutoMode | X,3 | 381 | 2 | Running mode Cooling:<br>0=Off<br>1=Manual<br>2=Auto |
| Ventilation1.Cor_CoolCoilManual | R,3 | 382 | 0 | Cooling controller output if manual mode |
| Ventilation4.Cor_HumidityPID_Select | X,3 | 383 | 2 | Running mode Humidification/Dehumidification:<br>0=Off<br>1=Manual<br>2=Auto |
| Ventilation4.Cor_HumidityPID_ManSet | R,3 | 384 | 0 | Humidification/Dehumidification controller output if manual mode |
| Ventilation1.Cor_HeatPumpAutoMode(0) | X,3 | 385 | 2 | Running mode P1-Heating:<br>0=Manual off<br>1=Manual on<br>2=Auto |
| Ventilation1.Cor_ExchPumpAutoMode | X,3 | 386 | 2 | Running mode P1-Exchanger:<br>0=Manual off<br>1=Manual on<br>2=Auto |
| Ventilation1.Cor_CoolPumpAutoMode | X,3 | 387 | 2 | Running mode P1-Cooling:<br>0=Manual off<br>1=Manual on<br>2=Auto |
| Ventilation1.Cor_FireDamperAutoMode | X,3 | 388 | 2 | Running mode fire damper:<br>0=Close<br>1=Open<br>2=Auto |
| Ventilation1.Cor_FreshAirDamperAutoMode | X,3 | 389 | 2 | Running mode fresh air damper:<br>0=Close<br>1=Open<br>2=Auto |
| Ventilation1.Cor_RecycleAirDamperAutoMode | X,3 | 390 | 2 | Running mode recirculation damper:<br>0=Close<br>1=Open<br>2=Auto |
| Ventilation1.Cor_ExtractAirDamperAutoMode | X,3 | 391 | 2 | Running mode extract air damper:<br>0=Close<br>1=Open<br>2=Auto |

| | | | | |
|---|---|---|---|---|
| TimePro. TimeGroupStatusFanFullSpeed | X,3 | 393 | 4 | Manual/Auto Full Speed time channel<br>0=Manual-Off<br>1=Manual-On<br>2=Forced Off<br>3=Forced On<br>4=Auto |
| TimePro. TimeGroupStatusFanHalfSpeed | X,3 | 394 | 4 | Manual/Auto Half Speed time channel<br>0=Manual-Off<br>1=Manual-On<br>2=Forced Off<br>3=Forced On<br>4=Auto |
| TimePro. TimeGroupStatusCor_ExtraTimeGroup1 | X,3 | 395 | 4 | Manual/Auto Timer output 1<br>0=Manual-Off<br>1=Manual-On<br>2=Forced Off<br>3=Forced On<br>4=Auto |
| TimePro. TimeGroupStatusCor_ExtraTimeGroup2 | X,3 | 396 | 4 | Manual/Auto Timer output 2<br>0=Manual-Off<br>1=Manual-On<br>2=Forced Off<br>3=Forced On<br>4=Auto |
| TimePro. TimeGroupStatusCor_ExtraTimeGroup3 | X,3 | 397 | 4 | Manual/Auto Timer output 3<br>0=Manual-Off<br>1=Manual-On<br>2=Forced Off<br>3=Forced On<br>4=Auto |
| TimePro. TimeGroupStatusCor_ExtraTimeGroup4 | X,3 | 398 | 4 | Manual/Auto Timer output 4<br>0=Manual-Off<br>1=Manual-On<br>2=Forced Off<br>3=Forced On<br>4=Auto |
| TimePro. TimeGroupStatusCor_ExtraTimeGroup5 | X,3 | 399 | 4 | Manual/Auto Timer output 5<br>0=Manual-Off<br>1=Manual-On<br>2=Forced Off<br>3=Forced On<br>4=Auto |
| Ventilation1.Cor_HumidityAutoMode | X,3 | 421 | 2 | Running mode humidity start signal<br>0=Off<br>1=On<br>2=Auto |
| Ventilation4.Cor_ExtraUnitPID1_Select(0) | X,3 | 437 | 2 | Manual/Auto Extra Unit Controller<br>0=Off<br>1=Manual<br>2=Auto |
| Ventilation4.Cor_ExtraUnitPID1_ManSet(0) | R,3 | 438 | 0 | Extra Unit Controller output if manual mode |

# 7. Alarm status

## 7.1. Alarm status

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| AlaData.AlaPt1_Status | X,4 | 71 | | Run Error Supply Air Fan<br>0=Not used<br>1=Normal<br>2=Blocked<br>3=Acknowledge<br>4=Not used<br>5=Cancelled<br>6=Not used<br>7=Alarm |
| AlaData.AlaPt2_Status | X,4 | 72 | | Run Error Exhaust Air Fan |
| AlaData.AlaPt3_Status | X,4 | 73 | | Run Error P1-Heater |
| AlaData.AlaPt4_Status | X,4 | 74 | | Run Error P1-Cooler |
| AlaData.AlaPt5_Status | X,4 | 75 | | Run Error P1-Exchanger |
| AlaData.AlaPt6_Status | X,4 | 76 | | Filter guard |
| AlaData.AlaPt7_Status | X,4 | 77 | | Flow guard |
| AlaData.AlaPt8_Status | X,4 | 78 | | External frost guard |
| AlaData.AlaPt9_Status | X,4 | 79 | | Deicing pressure guard |
| AlaData.AlaPt10_Status | X,4 | 80 | | Fire alarm |
| AlaData.AlaPt11_Status | X,4 | 81 | | External switch |
| AlaData.AlaPt12_Status | X,4 | 82 | | External alarm |
| AlaData.AlaPt13_Status | X,4 | 83 | | Supply Air control error |
| AlaData.AlaPt14_Status | X,4 | 84 | | Not used |
| AlaData.AlaPt15_Status | X,4 | 85 | | High supply air temp |
| AlaData.AlaPt16_Status | X,4 | 86 | | Low supply air temp |
| AlaData.AlaPt17_Status | X,4 | 87 | | Supply Air Fan max limit |
| AlaData.AlaPt18_Status | X,4 | 88 | | Supply Air Fan min limit |
| AlaData.AlaPt19_Status | X,4 | 89 | | High room temp |

| | | | | |
|---|---|---|---|---|
| AlaData.AlaPt20_Status | X,4 | 90 | | Low room temp |
| AlaData.AlaPt21_Status | X,4 | 91 | | High exhaust air temp |
| AlaData.AlaPt22_Status | X,4 | 92 | | Low exhaust air temp |
| AlaData.AlaPt23_Status | X,4 | 93 | | Electric heating is overheated |
| AlaData.AlaPt24_Status | X,4 | 94 | | Frost risk |
| AlaData.AlaPt25_Status | X,4 | 95 | | Low frost guard temp |
| AlaData.AlaPt26_Status | X,4 | 96 | | Low efficiency |
| AlaData.AlaPt27_Status | X,4 | 97 | | Sensor error outdoor temp |
| AlaData.AlaPt28_Status | X,4 | 98 | | Analogue deicing |
| AlaData.AlaPt29_Status | X,4 | 99 | | Rotation guard exchanger |
| AlaData.AlaPt30_Status | X,4 | 100 | | Fire damper is out of operation |
| AlaData.AlaPt31_Status | X,4 | 101 | | Supply Air Fan control error |
| AlaData.AlaPt32_Status | X,4 | 102 | | Exhaust Air Fan control error |
| AlaData.AlaPt33_Status | X,4 | 103 | | Supply Air Fan external operation |
| AlaData.AlaPt34_Status | X,4 | 104 | | Exhaust Air Fan external operation |
| AlaData.AlaPt35_Status | X,4 | 105 | | Ventilation Manual mode |
| AlaData.AlaPt36_Status | X,4 | 106 | | Manual supply air control |
| AlaData.AlaPt37_Status | X,4 | 107 | | Manual Supply Air Fan mode |
| AlaData.AlaPt38_Status | X,4 | 108 | | Manual Supply Air Fan freq control |
| AlaData.AlaPt39_Status | X,4 | 109 | | Manual Exhaust Air Fan mode |
| AlaData.AlaPt40_Status | X,4 | 110 | | Manual Exhaust Air Fan freq control |
| AlaData.AlaPt41_Status | X,4 | 111 | | Manual heater control |
| AlaData.AlaPt42_Status | X,4 | 112 | | Manual cooler control |
| AlaData.AlaPt43_Status | X,4 | 113 | | Manual exchanger control |
| AlaData.AlaPt44_Status | X,4 | 114 | | Manual P1-Heater |
| AlaData.AlaPt45_Status | X,4 | 115 | | Manual P1-Cooler |
| AlaData.AlaPt46_Status | X,4 | 116 | | Manual P1-Exchanger |
| AlaData.AlaPt47_Status | X,4 | 117 | | Manual fire damper |
| AlaData.AlaPt48_Status | X,4 | 118 | | Internal battery error |
| AlaData.AlaPt49_Status | X,4 | 137 | | Sensor error Supply Air temp |
| AlaData.AlaPt50_Status | X,4 | 138 | | Sensor error Exhaust Air temp |
| AlaData.AlaPt51_Status | X,4 | 139 | | Sensor error Room temp 1 |
| AlaData.AlaPt52_Status | X,4 | 140 | | Sensor error Room temp 2 |
| AlaData.AlaPt53_Status | X,4 | 141 | | Sensor error Extract Air temp |
| AlaData.AlaPt54_Status | X,4 | 142 | | Sensor error Extra sensor |
| AlaData.AlaPt55_Status | X,4 | 143 | | Sensor error SAF pressure |
| AlaData.AlaPt56_Status | X,4 | 144 | | Sensor error EAF pressure |
| AlaData.AlaPt57_Status | X,4 | 145 | | Sensor error Deicing temp |

| | | | | |
|---|---|---|---|---|
| AlaData.AlaPt58_Status | X,4 | 146 | | Sensor error Frost Protection temp |
| AlaData.AlaPt59_Status | X,4 | 147 | | Sensor error CO2 |
| AlaData.AlaPt60_Status | X,4 | 148 | | Sensor error Humidity room |
| AlaData.AlaPt61_Status | X,4 | 149 | | Sensor error Humidity duct |

# 7.2. Alarm points

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Ventilation2.Cor_AlaPt(1) | L,2 | 33 | | Run Error Supply Air Fan<br>0=No alarm<br>1=Alarm |
| Ventilation2.Cor_AlaPt(2) | L,2 | 34 | | Run Error Exhaust Air Fan |
| Ventilation2.Cor_AlaPt(3) | L,2 | 35 | | Run Error P1-Heater |
| Ventilation2.Cor_AlaPt(4) | L,2 | 36 | | Run Error P1-Cooler |
| Ventilation2.Cor_AlaPt(5) | L,2 | 37 | | Run Error P1-Exchanger |
| Ventilation2.Cor_AlaPt(6) | L,2 | 38 | | Filter guard |
| Ventilation2.Cor_AlaPt(7) | L,2 | 39 | | Flow guard |
| Ventilation2.Cor_AlaPt(8) | L,2 | 40 | | External frost guard |
| Ventilation2.Cor_AlaPt(9) | L,2 | 41 | | Deicing pressure guard |
| Ventilation2.Cor_AlaPt(10) | L,2 | 42 | | Fire alarm |
| Ventilation2.Cor_AlaPt(11) | L,2 | 43 | | External switch |
| Ventilation2.Cor_AlaPt(12) | L,2 | 44 | | External alarm |
| Ventilation2.Cor_AlaPt(13) | L,2 | 45 | | Supply Air control error |
| Ventilation2.Cor_AlaPt(14) | L,2 | 46 | | Deviation Humidity control |
| Ventilation2.Cor_AlaPt(15) | L,2 | 47 | | High supply air temp |
| Ventilation2.Cor_AlaPt(16) | L,2 | 48 | | Low supply air temp |
| Ventilation2.Cor_AlaPt(17) | L,2 | 49 | | Supply Air Fan max limit |
| Ventilation2.Cor_AlaPt(18) | L,2 | 50 | | Supply Air Fan min limit |
| Ventilation2.Cor_AlaPt(19) | L,2 | 51 | | High room temp |
| Ventilation2.Cor_AlaPt(20) | L,2 | 52 | | Low room temp |
| Ventilation2.Cor_AlaPt(21) | L,2 | 53 | | High exhaust air temp |
| Ventilation2.Cor_AlaPt(22) | L,2 | 54 | | Low exhaust air temp |
| Ventilation2.Cor_AlaPt(23) | L,2 | 55 | | Electric heating is overheated |
| Ventilation2.Cor_AlaPt(24) | L,2 | 56 | | Frost risk |
| Ventilation2.Cor_AlaPt(25) | L,2 | 57 | | Low frost guard temp |
| Ventilation2.Cor_AlaPt(26) | L,2 | 58 | | Low efficiency |

| | | | | |
|---|---|---|---|---|
| Ventilation2.Cor_AlaPt(27) | L,2 | 59 | | Sensor error outdoor temp |
| Ventilation2.Cor_AlaPt(28) | L,2 | 60 | | Analogue deicing |
| Ventilation2.Cor_AlaPt(29) | L,2 | 61 | | Rotation guard exchanger |
| Ventilation2.Cor_AlaPt(30) | L,2 | 62 | | Fire damper is out of operation |
| Ventilation2.Cor_AlaPt(31) | L,2 | 63 | | Supply Air Fan control error |
| Ventilation2.Cor_AlaPt(32) | L,2 | 64 | | Exhaust Air Fan control error |
| Ventilation2.Cor_AlaPt(33) | L,2 | 65 | | Supply Air Fan external operation |
| Ventilation2.Cor_AlaPt(34) | L,2 | 66 | | Exhaust Air Fan external operation |
| Ventilation2.Cor_AlaPt(35) | L,2 | 67 | | Ventilation Manual mode |
| Ventilation2.Cor_AlaPt(36) | L,2 | 68 | | Manual supply air control |
| Ventilation2.Cor_AlaPt(37) | L,2 | 69 | | Manual Supply Air Fan mode |
| Ventilation2.Cor_AlaPt(38) | L,2 | 70 | | Manual Supply Air Fan freq control |
| Ventilation2.Cor_AlaPt(39) | L,2 | 71 | | Manual Exhaust Air Fan mode |
| Ventilation2.Cor_AlaPt(40) | L,2 | 72 | | Manual Exhaust Air Fan freq control |
| Ventilation2.Cor_AlaPt(41) | L,2 | 73 | | Manual heater control |
| Ventilation2.Cor_AlaPt(42) | L,2 | 74 | | Manual cooler control |
| Ventilation2.Cor_AlaPt(43) | L,2 | 75 | | Manual exchanger control |
| Ventilation2.Cor_AlaPt(44) | L,2 | 76 | | Manual P1-Heater |
| Ventilation2.Cor_AlaPt(45) | L,2 | 77 | | Manual P1-Cooler |
| Ventilation2.Cor_AlaPt(46) | L,2 | 78 | | Manual P1-Exchanger |
| Ventilation2.Cor_AlaPt(47) | L,2 | 79 | | Manual fire damper |
| Ventilation2.Cor_AlaPt(48) | L,2 | 80 | | Internal battery error |
| Ventilation2.Cor_AlaPt(49) | L,2 | 90 | | Sensor error Supply Air temp |
| Ventilation2.Cor_AlaPt(50) | L,2 | 91 | | Sensor error Exhaust Air temp |
| Ventilation2.Cor_AlaPt(51) | L,2 | 92 | | Sensor error Room temp 1 |
| Ventilation2.Cor_AlaPt(52) | L,2 | 93 | | Sensor error Room temp 2 |
| Ventilation2.Cor_AlaPt(53) | L,2 | 94 | | Sensor error Extract Air temp |
| Ventilation2.Cor_AlaPt(54) | L,2 | 95 | | Sensor error Extra sensor |
| Ventilation2.Cor_AlaPt(55) | L,2 | 96 | | Sensor error SAF pressure |
| Ventilation2.Cor_AlaPt(56) | L,2 | 97 | | Sensor error EAF pressure |
| Ventilation2.Cor_AlaPt(57) | L,2 | 98 | | Sensor error Deicing temp |
| Ventilation2.Cor_AlaPt(58) | L,2 | 99 | | Sensor error Frost Protection temp |
| Ventilation2.Cor_AlaPt(59) | L,2 | 100 | | Sensor error CO2 |
| Ventilation2.Cor_AlaPt(60) | L,2 | 101 | | Sensor error Humidity room |
| Ventilation2.Cor_AlaPt2(1) | L,2 | 102 | | Sensor error Humidity duct |
| Ventilation2.Cor_ReservedActive(10) | L,2 | 103 | | Not used |
| Ventilation2.Cor_ReservedActive(10) | L,2 | 104 | | Not used |
| Ventilation2.Cor_ReservedActive(10) | L,2 | 105 | | Not used |

| | | | | |
|---|---|---|---|---|
| Ventilation2.Cor_ReservedActive(10) | L,2 | 106 | | Not used |
| Ventilation2.Cor_ReservedActive(10) | L,2 | 107 | | Not used |
| Ventilation2.Cor_ReservedActive(10) | L,2 | 108 | | Not used |
| Ventilation2.Cor_ReservedActive(10) | L,2 | 109 | | Not used |
| Ventilation2.Cor_ReservedActive(10) | L,2 | 110 | | Not used |
| Ventilation2.Cor_ReservedActive(10) | L,2 | 111 | | Not used |
| Ventilation2.Cor_ReservedActive(10) | L,2 | 112 | | Not used |

## 7.3. Alarm Acknowledging, Blocking and Unblocking

| Signal name | Type | Modbus address | Default value | Description |
|---|---|---|---|---|
| Alarms.AlaAcknow | X,3 | 400 | 255 | External alarm acknowledge by setting this signal to the alarm number that should be acknowledge. |
| Alarms.AlaBlock | X,3 | 401 | 255 | External alarm blocking by setting this signal to the alarm number that should be blocked. |
| Alarms.AlaUnBlock | X,3 | 402 | 255 | External alarm unblocking by setting this signal to the alarm number that should be unblocked. |
| Ventilation1.Cor_AlaAcknowAll | L,1 | 3 | 0 | Command to acknowledge all alarms |